

Acknowledgements

The SEMSWA Grading Erosion and Sediment Control (GESC) Manual is an adaptation of the Douglas County GESC Manual. SEMSWA finds the Douglas County GESC Program and Manual to be State of the Art in the Field of Erosion and Sediment Control, and has determined it to be extremely appropriate for use in the City. SEMSWA appreciates the amount of effort and expertise that went into the development of the original Douglas County GESC program and GESC manual.

The SEMSWA Water Quality and Land Development Coordination groups wish to thank the following individuals for their assistance and contributions to make SEMSWA's adaptation of the Manual possible.

Arapahoe County Public Works Project Managers
Cindy Edwards, PE, Stormwater Engineer III
Dan Olsen, Stormwater Engineer I

City Land Use Services Project Managers
Gayle Sturdivant, PE, Engineering Manager
Gary Johnson, PE, Land Disturbance Coordinator

City/County Staff
Dave Schmit, PE, Director, Department of Public Works
Jim Pankonin, PE, Engineering Division Manager
Steve Gardner, PE, Program Manager, Stormwater Management Division
Lanae Raymond, Stormwater Engineer II
Jerry Rearick, Stormwater Engineer II
Chuck Haskins, PE, Program Manager, Land Development Services
Stacey Thompson, Engineer II
Jeff Scott, Chief Engineering Inspector
Jeff Rice, PE, Project Engineer
Rich Kantrowitz, Engineering Coordinator
Lou Kingsley, Inspector

Douglas County
Erik Nelson, Project Engineer, Principal GESC Author

Technical Assistance
Tracy Bolger, PE, Muller Engineering
Jim Wulliman, PE, Muller Engineering
Jacob Marquez, Moser Engineering

In addition, SEMSWA would like to thank all those who provided a review of the draft manual.

Table of Contents

Section 1. Regulatory and Permitting

1.0	Overview of Section 1	1-1
1.1	The GESC Permit	1-2
1.2	Reasons for the GESC Permit	1-2
1.3	Legislative Mandate	1-3
1.3.1	NPDES Regulations	1-3
1.3.2	Cherry Creek Reservoir Control Regulation No. 72	1-4
1.4	Authorization of the GESC Manual	1-5
1.4.1	Jurisdiction	1-5
1.4.2	Amendments and Revisions	1-5
1.4.3	Enforcement Responsibility	1-5
1.4.4	Review and Acceptance	1-5
1.4.5	Interpretation	1-5
1.4.6	Relationship to Other Standards	1-6
1.5	State Permitting	1-6
1.5.1	Stormwater Management Plan	1-6
1.5.2	Construction Dewatering Permits	1-6
1.5.3	Air Quality Plans	1-7
1.6	Federal Permitting	1-7
1.6.1	FEMA Map Revisions	1-7
1.6.2	Section 404 Permitting	1-7
1.6.3	U.S. Fish and Wildlife Service Threatened and Endangered Species Clearance	1-8
1.6.4	Migratory Bird Treaty Act	1-8

Section 2. Submittal and Permit Process

2.0	Overview of Section 2	2-1
2.1	Projects Requiring a GESC Permit	2-3
2.1.1	Projects that Require a GESC Permit	2-3
2.1.2	Projects that Require a Low-Impact GESC Permit	2-3
2.1.3	Projects that Do Not Require a GESC Permit	2-4
2.1.4	Projects Covered Under Other Permits	2-5
2.2	Types of GESC Permits	2-5
2.2.1	Standard GESC Permit	2-5
2.2.2	Low Impact GESC Permit	2-5
2.2.3	Temporary Batch Plant/GESC Permit	2-5
2.3	Who Obtains a GESC Permit?	2-5
2.4	What Steps are Included in the GESC Permit Process?	2-6
2.5	Projects that Require a Standard GESC Permit	2-6
2.6	Who Prepares GESC Plans?	2-7
2.7	Presubmittal Meeting	2-7
2.8	Types of GESC Drawings	2-8
2.8.1	Small Site and Utility GESC Drawing	2-8
2.8.2	Staged GESC Drawing	2-8
2.8.3	Staged and Phased GESC Drawing	2-9
2.9	Other SEMSWA and City Plans and Permits	2-10
2.9.1	Submittal Packages	2-10
2.9.2	Planning Submittals	2-10
2.9.3	Accelerated Planning Submittals	2-11
2.9.4	Land Use Services Submittals	2-11
2.9.5	Review Fees	2-12
2.9.6	Drainage Plans	2-12

Table of Contents

Section 2. Submittal and Permit Process, continued

2.9.7	Right-of-Way Use Permit	2-13
2.9.8	Construction Permit	2-13
2.9.9	Floodplain Development Permit	2-13
2.10	Submittal of the GESC Plan and Report	2-14
2.11	Plan and Report Revisions Based on SEMSWA Comments	2-14
2.12	Preliminary Acceptance of the GESC Plan and Report	2-14
2.13	Final Acceptance of the GESC Plan and Report	2-14
2.13.1	Signed GESC Drawings and Report	2-14
2.13.2	GESC Field Manual	2-15
2.14	Applying for a GESC Permit	2-15
2.15	Permit Fees	2-15
2.16	Posting Collateral	2-15
2.16.1	General	2-15
2.16.2	Amount of Collateral	2-15
2.16.3	Forms of Collateral	2-16
2.16.4	Expiration of Collateral	2-16
2.17	Duration of GESC Permits	2-16
2.18	Transfer of GESC Permits	2-16
2.19	GESC Permits for Single Family Residential Projects	2-17
2.19.1	GESC Permitting for Single Family Residential Projects	2-17
2.19.2	Developer's Responsibilities for Single Family Residential Projects	2-18
2.19.3	New Owner's/Builder's Responsibilities for Single Family Residential Projects	2-19
2.19.4	Individual Lot Owner's Responsibilities for Single Family Residential Projects	2-20
2.20	GESC Permits for Multi-lot Development Projects	2-20
2.20.1	GESC Permitting for Multi-lot Development Projects	2-20
2.20.2	Developer's Responsibilities for Multi-lot Development Projects	2-21
2.20.3	New Owner's Responsibilities for Multi-lot Development Projects	2-22
2.20.4	Builder's Responsibilities for Multi-lot Development Projects	2-22

Section 3. Plan & Report Submittal Requirements

3.0	Overview of Section 3	3-1
3.1	Standard GESC Plan Drawing Requirements	3-2
3.1.1	GESC Drawing Cover Sheet	3-2
3.1.2	GESC Drawing Index Sheet	3-3
3.1.3	Initial GESC Drawing	3-3
3.1.4	Interim GESC Drawing	3-4
3.1.5	Final GESC Drawing	3-5
3.1.6	GESC Plan Standard Notes and Details	3-6
3.1.7	GESC Drawing and Report Checklist	3-6
3.1.8	Drawing Requirements for Utility GESC Drawings	3-6
3.1.9	Drawing Requirements for Staged and Phased GESC Drawings	3-6

Table of Contents

Section 3. Plan & Report Submittal Requirements, continued

3.1.10	Submittal Requirements for Related Plans	3-6
3.2	Standard GESC Report Requirements	3-6
3.3	Engineer's Cost Estimate	3-8
3.3.1	Engineer's Cost Estimate	3-8
3.3.2	Phased Projects	3-9
3.4	Variances	3-9
3.4.1	Variance and Appeal Procedures	3-9
3.4.2	Variance Criteria	3-10
3.4.3	Burden of Proof	3-10
3.4.4	Comprehensive Grading Plan	3-11
3.4.5	Permitting Requirements	3-11

Section 4. Grading Criteria, Ten Elements of an Effective GESC Plan, BMP Sizing

4.0	Overview of Section 4	4-1
4.1	Grading Guidance and Criteria	4-2
4.1.1	Preservation Areas	4-2
4.1.2	Slopes and Retaining Walls	4-2
4.1.3	Stockpiles	4-3
4.1.4	Departures in Grade from Existing Conditions	4-4
4.1.5	Earthwork Balance	4-4
4.1.6	Site Drainage	4-4
4.2	Principles of Erosion and Sedimentation	4-4
4.2.1	Erosion	4-4
4.2.2	Sedimentation	4-6
4.3	BMPs to Address Erosion and Sediment	4-7
4.3.1	Standard Detail Number and Identifier	4-7
	Table 4-1. Erosion and Sediment Control BMPs	4-8
4.3.2	Type of Control	4-9
4.3.3	Phase of Construction	4-9
4.3.4	GESC Drawings are to Use the Standard BMPs	4-9
4.3.5	Use of Alternative or Innovative BMPs	4-10
4.3.6	GESC Plan Standard Notes and Details	4-10
4.3.7	Selecting BMPs for the GESC Drawings	4-11
4.4	Ten Elements of an Effective GESC Plan	4-11
	Figure 4.1. Ten Elements of an Effective GESC Plan	4-13
4.5	Element 1. Preserve and Stabilize Drainageways	4-14
4.5.1	Drainageways Shall Not be Filled, Regraded, or Realigned	4-14
4.5.2	Ample Freeboard Above the 100-year Floodplain Shall be Provided	4-15
4.5.3	Existing Drainageways Shall be Stabilized	4-15
4.5.4	Disturbance to Existing Drainageways Shall be Minimized and Quickly Restored	4-16
4.5.5	Any New Drainageway Shall be Designed and Stabilized	4-18
4.6	Element 2. Avoid the Clearing and Grading of Sensitive Areas	4-19
4.7	Element 3. Balance Earthwork On Site	4-19
4.8	Element 4. Limit the Size of Grading Phases	

Table of Contents

Section 4. Grading Criteria, Ten Elements of an Effective GESC Plan, BMP Sizing, continued

	to Reduce Soil Exposure	4-20
4.9	Element 5. Stabilize Exposed Soils in a Timely Manner	4-21
4.10	Element 6. Implement Effective Perimeter Controls	4-22
4.10.1	Upslope Perimeters	4-22
4.10.2	Downslope Perimeters	4-22
4.11	Element 7. Use Sediment Basins for Areas Exceeding 1.0 Acre	4-24
4.12	Element 8. Protect Steep Slopes	4-25
4.12.1	Proposed Slopes Shall be No Steeper than 3 to 1	4-25
4.12.2	Runoff Shall be Diverted Away from Steep Slopes	4-25
4.12.3	Terracing Shall be Incorporated into the Grading of Steep Slopes	4-26
4.13	Element 9. Protect Inlets, Storm Sewer Outfalls, and Culverts	4-26
4.14	Element 10. Provide Access and General Construction Controls	4-27
4.14.1	Limits of Construction (LOC)	4-27
4.14.2	Construction Fence (CF)	4-27
4.14.3	Vehicle Tracking Control (VTC)	4-27
4.14.4	Stabilized Staging Area (SSA)	4-28
4.14.5	Concrete Washout Area (CWA)	4-28
4.14.6	Stockpile Areas	4-28
4.14.7	Temporary Access Roads	4-28
4.15	Design and Sizing Criteria for BMPs	4-28
4.15.1	Check Dam (CD) and Reinforced Check Dam (RCD)	4-29
4.15.2	Compost Blanket (CB) and Compost Filter Berm (CFB)	4-29
4.15.3	Concrete Washout Area (CWA)	4-29
4.15.4	Construction Fence (CF) and Construction Markers (CM)	4-29
4.15.5	Dewatering (DW)	4-30
4.15.6	Diversion Ditch (DD)	4-30
4.15.7	Erosion Control Blanket (ECB)	4-30
	Table 4.2. Erosion Control Blanket Type	4-31
	Figure 4.2. Erosion Control Blanket Design Criteria	4-32
4.15.8	Inlet Protection (IP)	4-33
4.15.9	Reinforced Rock Berm (RRB)	4-33
4.15.10	Sediment Basin (SB)	4-33
	Table 4-3. Sizing Information for Standard Sediment Basin	4-34
4.15.11	Sediment Control Log (SCL)	4-34
4.15.12	Sediment Trap (ST)	4-34
4.15.13	Seeding (SE) and Mulching (MU)	4-35
4.15.14	Silt Fence (SF)	4-36
	Table 4-4. Silt Fence on Slope	4-37
4.15.15	Temporary Slope Drain (TSD)	4-38
4.15.16	Stabilized Staging Area (SSA)	4-38
4.15.17	Surface Roughening (SR)	4-38

Table of Contents

Section 4. Grading Criteria, Ten Elements of an Effective GESC Plan, BMP Sizing, continued

4.15.18	Stream Crossing (SC)	4-38
4.15.19	Terracing (TER)	4-39
4.15.20	Vehicle Tracking Control (VTC)	4-39
4.15.21	Vehicle Tracking Control with Wheel Wash (WW)	4-39

Section 5. Field Process and Enforcement

5.0	Overview of Section 5	5-1
5.1	The GESC Manager	5-3
5.1.1	Responsibilities of the GESC Manager	5-3
5.1.2	Alternate GESC Manager	5-3
5.1.3	Availability of the GESC Manager	5-3
5.1.4	Changing the GESC Manager or Alternate	5-3
5.2	Understanding the Requirements of the GESC Plan	5-4
5.2.1	Implementing the GESC Plan in the Field	5-4
5.2.2	Diligence Pays Off	5-4
5.2.3	Review of the GESC Field Manual, GESC Plan, and Related Plans and Permits	5-4
5.2.4	Documents that Shall Remain On Site	5-5
5.3	Preparation for the Preconstruction Meeting	5-5
5.3.1	Installation of Initial BMPs	5-5
5.3.2	Construction Shall Not Start	5-5
5.3.3	Scheduling the Preconstruction Meeting	5-5
5.4	Preconstruction Meeting	5-5
5.4.1	Attendees at the Preconstruction Meeting	5-5
5.4.2	General Meeting Agenda	5-6
5.4.3	Corrections to the BMPs	5-6
5.5	The Executed GESC Permit	5-7
5.5.1	Pick Up the Executed GESC Permit	5-7
5.6	Installation of Interim and Final BMPs	5-7
5.7	Permittee GESC Inspections	5-7
5.8	SEMSWA GESC Inspection Process	5-7
5.8.1	SEMSWA GESC Inspections	5-7
5.8.2	Mandatory SEMSWA Inspections	5-8
5.9	Violation and Enforcement	5-9
5.9.1	Penalties and Enforcement	5-9
5.9.2	Violations	5-9
5.9.3	Level I Violations	5-9
5.9.4	Level II Violations	5-10
5.9.5	Re-Inspection Fee	5-11
5.9.6	Notice of Violation	5-11
5.9.7	Stop Work Orders	5-11
5.9.8	SEMSWA GESC Regulation	5-12
5.10	Revocation of Collateral for Default of Permittee(s)	5-12
5.10.1	Default by Permittee(s)	5-13
5.10.2	Notice of Default	5-12
5.10.3	SEMSWA Right to Complete Subdivision Improvements	5-13
5.10.4	Use of Funds by SEMSWA	5-13
6.0	Overview of Section 6	6-1
6.1	General Construction Practices	6-2
6.1.1	Complying with Limits of Construction	6-2

Section 6. General Construction, BMP Installation, Maintenance

Table of Contents

Section 6. General Construction, BMP Installation, Maintenance, cont.

6.1.2	Street Cleaning	6-2
6.1.3	Dust Control	6-3
6.1.4	Stockpiles	6-3
6.1.5	Import and Export of Soil	6-3
6.1.6	Placement of Fill	6-3
6.1.7	Control of Water During Construction -Temporary Stream Diversion	6-4
6.1.8	Utility Construction	6-4
6.1.9	Construction Site Chemical Control	6-5
6.1.10	Properly Store, Handle, Apply and Dispose of Pesticides	6-6
6.1.11	Properly Store, Handle, Use and Dispose of Petroleum Products	6-6
6.1.12	Sanitary Facilities	6-7
6.1.13	Other Construction Site Pollutants	6-7
6.1.14	Spills Response	6-7
6.2	Correct Installation and Maintenance of BMPs	6-8
6.2.1	Check Dam (CD)	6-9
6.2.2	Compost Blanket (CB) and Compost Filter Berm (CFB)	6-10
6.2.3	Concrete Washout Area (CWA)	6-11
6.2.4	Construction Fence (CF) and Construction Markers (CM)	6-12
6.2.5	Dewatering (DW)	6-13
6.2.6	Diversion Ditch (DD)	6-14
6.2.7	Erosion Control Blanket (ECB)	6-15
6.2.8	Inlet Protection (IP)	6-16
6.2.9	Reinforced Check Dam (RCD)	6-18
6.2.10	Reinforced Rock Berm (RRB)	6-19
6.2.11	RRB for Culvert Protection (RRC)	6-20
6.2.12	Sediment Basin (SB)	6-21
6.2.13	Sediment Control Log (SCL)	6-22
6.2.14	Sediment Trap	6-23
6.2.15	Seeding (SE) and Mulching (MU)	6-24
6.2.16	Silt Fence (SF)	6-26
6.2.17	Stabilized Staging Area (SSA)	6-27
6.2.18	Surface Roughening Area (SR)	6-28
6.2.19	Temporary Slope Drain (TSD)	6-29
6.2.20	Temporary Stream Crossing (TSC)	6-30
6.2.21	Terracing (TER)	6-31
6.2.22	Vehicle Tracking Control (VTC)	6-32
6.2.23	Vehicle Tracking Control with Wheel Wash (WW)	6-33
6.2.24	Pond Maintenance and Sediment Removal (PM)	6-34
6.2.25	Street Maintenance (SM)	6-35
7.0	Overview of Section 7	7-1
7.1	Preparation for Initial Close-out Inspection	7-2
7.1.1	Initial Close-Out	7-2

Section 7. Project Close-Out

Table of Contents

Section 7. Project Close-Out, cont.

7.1.2	Preparing for Inspection	7-2
7.1.3	Certifications	7-2
7.1.4	Initial Close-Out Acceptance Form	7-3
7.1.5	Scheduling the Inspection	7-3
7.2	Initial Close-out Acceptance	7-3
7.2.1	Attendees	7-3
7.2.2	General Meeting Agenda	7-3
7.2.3	Detached Single-Family Residential Projects	7-3
7.2.4	Corrections to Site	7-4
7.2.5	Granting Initial Close-Out Acceptance	7-4
7.2.6	Reduction of Financial Collateral	7-4
7.3	Interim Between Initial Close-Out and Final Close-Out	7-4
7.3.1	Required Inspections and Maintenance	7-4
7.3.2	Required Vegetation Coverage	7-5
7.4	Final Close-Out	7-6
7.4.1	Vegetation Acceptance Inspection	7-6
7.4.2	Written Acceptance	7-6
7.4.3	Removal of On-Site BMPs	7-6
7.4.4	Certifications	7-6
7.4.5	Final Close-Out Acceptance Form	7-6
7.4.6	Final Close-Out Inspection	7-6
7.4.7	Reduction of Collateral Prior to Final Close-Out	7-7
7.5	Release of Collateral	7-7

Section 8. Low Impact GESC Permit

8.0	Overview of Section 8	8-1
8.1	Projects that Require a Low Impact GESC Permit	8-2
8.2	Low Impact GESC Permit Application and Drawings	8-2
8.2.1	Low Impact Permit Application Requirements	8-2
8.2.2	Low Impact Drawing Requirements	8-3
8.3	Submit Low Impact Application and Drawing; Address SEMSWA Comments	8-3
8.4	Pay Permit Fee and Submit Collateral	8-4
8.5	Review GESC Field Manual	8-4
8.6	Install Initial BMPs	8-4
8.7	Begin Construction	8-4
8.8	Address any GESC or Land Use Services Inspection Comments	8-4
8.9	Drill Seed and Crimp Mulch All Disturbed Areas	8-5
8.10	Schedule Vegetation Acceptance Inspection	8-5

Section 9. Single Family Residential Lot GESC Criteria

9.0	Overview of Section 9	9-1
9.1	Scope	9-2
9.2	Enforcement	9-2
9.3	Violations	9-2
9.4	New Owners Become Party to Project GESC Permit	9-2
9.5	Drawing Requirements	9-3
9.6	Grading and Drainage Requirements for Finished Grade	9-3
9.6.1	Lot Grading and Drainage	9-3
9.6.2	Drainage Certificate	9-4
9.7	Erosion and Sediment Control Requirements	9-4
9.7.1	Stabilization of Individual Lots	9-4

Table of Contents

Section 9. Single Family Residential Lot GESC Criteria, continued

9.7.2	Single Family Lot Erosion Control Plan	9-4
9.8	SEMSWA Inspections	9-6
9.9	Notification of Violation	9-6
9.9.1	Level I Violations	9-6
9.9.2	Level II Violations	9-7
9.9.3	Violation Mitigation	9-7
9.10	Single Family Residential Drainage, Erosion, and Sedimentation Control Certification	9-7
9.11	Homeowner Responsibility	9-8

Section 10. Special Requirements for Utility Construction

10.0	Overview of Section 10	10-1
10.1	Utility Construction	10-2
10.2	Utility Construction Requiring a GESC Permit	10-2
10.3	Utility Construction Covered Under a Street Cut and Right-of-Way Use Permit	10-3
10.3.1	Drawings	10-3
10.3.2	Collateral	10-3
10.3.3	Enforcement	10-3
10.3.4	General Construction Site Best Management Practices	10-3

Section 11. Temporary Batch Plant/GESC Permit

11.0	Overview of Section 11	11-1
11.1	Temporary Batch Plant/GESC Permit	11-2
11.1.1	Special Requirements for Temporary Batch Plant/GESC Permit	11-2
11.2	Submittal Requirements for Temporary Batch Plant/GESC Drawings	11-2
11.2.1	Submittal Requirements for Temporary Batch Plant/GESC Drawings	11-2

Appendices

Appendix A	Contact Information	
Appendix B	GESC Plan Standard Notes and Details	
Appendix C	Example GESC Drawings	
	◆ Small Site GESC Drawings	
	◆ Utility GESC Drawings	
	◆ Staged GESC Drawings	
	◆ Staged and Phased GESC Drawings	
	◆ Low-Impact GESC Drawings	
	◆ Temporary Batch Plant GESC Drawings	
Appendix D	Checklist for Developing a GESC Plan	
Appendix E	GESC Drawing and Report Checklist	
Appendix F	Engineer's Cost Estimate Spreadsheet for <i>Initial and Interim</i> BMPs	
Appendix G	Engineer's Cost Estimate Spreadsheet for <i>Final</i> BMPs	
Appendix H	SEMSWA GESC Approval Block	
Appendix I	Comprehensive Grading Plan	
Appendix J	Standard GESC Permit Application	
Appendix K	Low-Impact GESC Permit Application	
Appendix L	Irrevocable Letter of Credit Form	

Table of Contents

Appendices, continued

Appendix M	Example Hold Harmless Letter
Appendix N	Phasing Acceptance Sheet
Appendix O	Letter of GESC Permit Compliance
Appendix P	Initial Close-out Acceptance Forms <ul style="list-style-type: none">◆ Initial Close-out Acceptance Worksheet◆ Seeding and Mulching Certification◆ Topsoil Certification◆ Initial Close-Out GESC Inspections Certification◆ Detention/Water Quality Pond Volume Statement
Appendix Q	Final Close-out Acceptance Forms <ul style="list-style-type: none">◆ Final Close-Out Acceptance Worksheet◆ Final Close-Out GESC Inspections Certification◆ Vegetation Acceptance◆ Detention/Water Quality Pond Volume Statement
Appendix R	Request for Reduction of Collateral Form
Appendix S	Single Family Lot Certificates <ul style="list-style-type: none">◆ Single Family Lot Erosion Control Certificate◆ Drainage Certificate
Appendix T	Seed Mix Information
Appendix U	Temporary Batch Plant GESC Permit Application
Appendix V	Noxious Weeds